

Prepared for

Gilgandra Shire Council 361 OXLEY HIGHWAY GILGANDRA

20 May 2024

WATER & SEWER SERVICING REPORT



Prepared by:

WALLACE DESIGN GROUP PTY LTD

PO Box 23, CHARLESTOWN, NSW 2290

T: +61 2 4929 4109

E: aarons@wdegroup.com.au

Client Manager: Aaron Sanders Report Number:

23403

Version / Date: Ver.1 | 8.03.2024

Prepared for:

GILGANDRA SHIRE COUNCIL

Suraj Perera PO Box 23 Gilgandra NSW 2827

T: (02) 6847 2521

E:

sperera@gilgandra.nsw.gov.au

Client Contact: Suraj Perera



Important Note

This document is to be submitted to Gilgandra Shire Council to provide advice on the water and sewer servicing of the project. The document may only be used for the purposes for which it was commissioned and in accordance with the Terms of Engagement for the commission. Unauthorised copying or use of this document in any form whatsoever is prohibited.

Apart from fair dealing for the purposes of private study, research, criticism, or review as permitted under the Copyright Act, no part of this report, its attachments or appendices may be reproduced by any process without the written consent of Wallace Design Group Pty Ltd ("WDG" or "we"). All enquiries should be directed to WDG.

We have prepared this report for Gilgandra Shire Council ("Client") for the specific purpose for which it is supplied ("Purpose"). This report is strictly limited to the purpose including the facts and matters stated within it and is not to be used, directly or indirectly, for any other application, purpose, use or matter.

In preparing this report WDG has made certain assumptions. We have assumed that all information and documents provided to us by the Client or as a result of a specific request or enquiry were complete, accurate and up-to-date. Where we have obtained information from a government register or database, we have assumed that the information is accurate. Where an assumption has been made, we have not made any independent investigations with respect to the matters the subject of that assumption. As such we would not be aware of any reason if any of the assumptions were incorrect.

This report is presented without the assumption of a duty of care to any other person ("Third Party") (other than the Client and parties required for the purpose of the report). The report may not contain sufficient information for the purposes of a Third Party or for other uses. Without the prior written consent of WDG:

- (a) this report may not be relied on by a Third Party; and
- (b) WDG will not be liable to a Third Party for any loss, damage, liability or claim arising out of or incidental to a Third Party publishing, using or relying on the facts, content, opinions or subject matter contained in this report.

If a Third Party uses or relies on the facts, content, opinions or subject matter contained in this report with or without the consent of WDG, WDG disclaims all risk from any loss, damage, claim or liability arising directly or indirectly, and incurred by any third party, from the use of or reliance on this report.

In this note, a reference to loss and damage includes past and prospective economic loss, loss of profits, damage to property, injury to any person (including death) costs and expenses incurred in taking measures to prevent, mitigate or rectify any harm, loss of opportunity, legal costs, compensation, interest and any other direct, indirect, consequential or financial or other loss.

Document Status

Version	Purpose of Document	Orig	Review	Review Date
Ver 2	Client Review	VS	AS	20.05.2024
Ver.1	Client Review	VS	AS	6 May 2024

Approval for Issue

Name	Signature	Date
Aaron Sanders		



Contents

Tern	ns and Abbr	reviations	1
1.0	Introduction	ion	2
	1.1	Background	2
	1.2	Development	2
2.0	Water		3
	2.1	Design Water Demands	3
		Water Modelling	
3.0	Sewer		5
	3.1	Design Sewerage Loading	6
4.0	Conclusio	on	7
Арр	endix 1		8
Sub	division Site	e Plan	8

Appendices

Appendix 1 Subdivision Site Plan

Appendix 2 Water Infrastructure

Appendix 3 Water Modelling Outputs

Appendix 4 Sewer Infrastructure

Appendix 5 Estimating Spreadsheets



Terms and Abbreviations

AHD	Australian Height Datum
DA	Development Application
GSC	Gilgandra Shire Council
RL	Reduced Level
SPS	Sewer Pump Station
WDG	Wallace Design Group Pty Ltd



1.0 Introduction

Wallace Design Group Pty Ltd (WDG) has been engaged by Gilgandra Shire Council (GSC) to prepare a water and sewer servicing report to support the development of a new industrial development at Lot 1 DP 1070081 361 Oxley Highway, Gilgandra.

The proposed industrial subdivision site will be rezoned from its current zoning RU1(Primary Production) to E4 (General Industrial). Prior to rezoning Council requires sufficient information on water and sewer services such that it can conclude that the land can be feasibly and economically serviced. Council requirements are to show that future development will maximise cost-effective and efficient use of infrastructure by focusing development on existing infrastructure or promoting co-location of new infrastructure.

This report addresses the provision of water and sewer services to the proposed development.

I.I Background

Gilgandra Shire Council is submitting a Planning Proposal to rezone some rural land so that it can be used for employment purposes. Gilgandra Shire Council (GSC) is the proponent with Council intending to purchase part of the subject land for industrial development. The subject land to be zoned for employment purposes is Lot 1 DP 1070081 and part Lot 2 DP 1070081, Oxley Highway, Gilgandra.

The land proposed for rezoning is approximately 52 hectares in total and will be developed in two stages: Council intends to purchase the 21-hectare fronting the Oxley Highway and develop as Stage 1 industrial development, with the balance of approximately 31 hectares to be retained by the landowner and for future potential industrial growth, Stage 2.

The stage 1 is an industrial subdivision which consists of 27 Lots. Stage 2 will be developed as solar farm with possible future industrial subdivision in approximately 35 years. Points of connection to the water and sewer systems will be left for proposed Stage 2.

This project is an initiative of the Gilgandra Shire Council in its aim to show that future development will maximise the cost-effective and efficient use of infrastructure by focusing development on existing infrastructure or promoting co-location of new infrastructure.

I.2 Development

Stage 1:

In stage 1, GSC is preparing for the development of a new industrial subdivision of approximately 20.97ha. The proposed development has a direct frontage of Oxley Highway within an 80km/h zone. The development consisting of 27 lots including the proposed council water treatment plant and the construction of internal roads, drainage structures and reserve for stormwater detention basin.

It is expected, lots in Stage 1 will be constructed immediately and offered for sale in 2025.

Stage 2:

Stage 2 is approximately 31.12h and only for rezoning purpose at this phase. The proposed development of Stage 2 will be a future long term industrial growth and estimated to have 25-30 lots. Industrial purpose on this land may not be for approximately 35 years. In the interim it is expected that Stage 2 will be developed as a solar farm.

A plan of the site is attached at **Appendix 1.**



Methodology

Advice on the existing water and sewer systems servicing the area and the proposed subdivision layout have been provided by GSC. In terms of a proposed connection points, GSC preferred options are to connect sewer into the existing rising main that crosses the Oxley Highway and water into the existing 250mm main that runs along the Oxley Highway.

2.0 Water

The proposed development is within the Gilgandra Shire Council. The closest water connection point is the DN250 main running along the Oxley Highway providing the development site with a full frontage.

The proposed industrial subdivision will be serviced by the extension of a 150mm watermain connecting to the existing 250mm main in the Oxley Highway in two locations thus providing security of supply to the development.

The construction of approximately 928m x 150mm watermain will be required to provide all proposed lots with a point of connection to the reticulated water system.

A plan indicating the existing water infrastructure and the proposed watermain extension for the development site is attached at **Appendix 2.**

The cost of the proposed watermains is estimated to be in the order of \$200,000.00.

A copy of the preliminary estimating spreadsheet is attached at Appendix 5.

2.1 Design Water Demands

To estimate design flows, values from the Water Services Association of Australia (WSAA) Water Supply Code of Australia WSA03-2002-2.3 Hunter Water Edition Version 2.1 have been adopted. Theoretical loadings have been determined based on Kl/Ha/day for light industrial development. The criteria used to determine the theoretical water design flows are summarised below:

Industrial

- Average Demand for new industrial developments 11.5 KI/Ha/day
- Average Day Demand (L/s) = 2.52
- Peak Day Demand (L/s) = ADD x PDD Factor x Diversity Factor
- Peak Day Factor Industrial 1.20
- Diversity Factor 2.653 x ET^{0.1067}
- Extreme Day Demand (L/s) = PDD x 1.15
- Unaccounted Water = 15% of Average Day Demand

Design flows based on the potential lot yield are shown in **Table 1** below:



Table 1 Total Theoretical Water Loadings

Development Type	Area	Average Day Demand (I/s)	Peak Day Demand (I/s)	Extreme Day Demand (I/s)	Unaccounted Water (I/s)
Industrial Lots	18.94	2.52	4.36	5.02	0.38
	Fire Flows	N/A	8.00	N/A	N/A

2.2 Water Modelling

Pipe sizing has been confirmed with computer modelling using 'EPANET 2.2'. The EPANET software has been developed by the Water Supply & Water Resources Division at the National Risk Management Research Laboratory of the US Environmental Protection Agency.

Water modelling has been undertaken based on information provided by GSC. A pressure of 20.41m was observed at 298 Warren Rd (Oxley Hwy).

Modelling of the water flows in the area indicate that the pressure at peak demand (13:30) at Node 3, the highest point in the proposed subdivision would be 23.17m

The modelling indicates that with fireflows of 8 l/s a pressure of 22.71m at Node 3, the highest point in the proposed subdivision.

Details of the modelling network and results are attached at Appendix 3.



3.0 Sewer

The proposed development is within the Gilgandra township and the catchment area of the SPS No. SPS0008 located at Naden Drive. GSC is planning to build a new Sewer Pump Station (SPS) within the proposed subdivision site. The survey provided by GSC, has determined that there is 4.5m fall from South-East to North-West on proposed development. The proposed sewer can be drained under gravity sewer system by installing a new sewer pump station (SPS) at south-western corner of the Stage 1. The provision of the gravity reticulation sewer system detailed will adequately service the proposed subdivision.

Information provided by Council; it is expected that there will be a sufficient capacity in the Gilgandra Sewage Treatment Plant to cater for the development. On councils' advice, the sewer loading should be based on 6ET/Ha, for industrial subdivision, which will create 108 ETs in Stage 1 and 186 ETs in Stage 2. It is noted that it is proposed to construct a solar farm on Stage 2 and sewer connection would not be required for approximately 35 years.

It is proposed that the civil works and rising main for the proposed SPS be constructed to service the ultimate development with pumps and electrical being constructed to service Stage 1 only. It is anticipated that both pumps and electrics would need replacement within the 35-year time frame before Stage 2 was connected to the sewer.

The design incorporates a new SPS with rising main connecting to existing SPS0008. The construction of approximately 729.62m x 150mm Rising main connecting to an existing 100mm rising main located in Oxley Highway will be the point of connection to the reticulated sewer system.

Proposed Works Reticulation Sewermain

957.55m x 150mm 200.85m x 450mm

SPS (duty and standby pumps)

1.8 m diameter x 6.30 m deep Pumps 10 L/s @ 11.30m (2 x 2KW pumps) Control Volume – 0.90 m³ Control Depth – 0.35 m

Emergency Storage

Wet Well is to be sized accordingly to ensure it can accommodate necessary emergency storage if required.

(Note: During the detailed design stage, if emergency storage is contained within wet wells, the 450mm sewermain may be reduce the size of sewermain.)

Rising Main

729.62m x 150 mm

Velocity - 0.57 m/s

Friction Losses - 2.00m

Static Head - 9.30m

Total Head - 11.30m

Detention Time - 3.24 Hrs - odour control will **not** be required.



Details of the works required to provide the proposed development with sewer services that meet GSC requirements are listed below:

Stage	ET	Cumulative ET	Required Infrastructure
1	108	108	Gravity sewer, construction of SPS in Lot 12 and rising main.
2	186	294	Gravity sewer connecting to SPS in Lot 12.

The capital cost for the required sewer network is estimated to be in the order of \$1,355,000.

A copy of the preliminary estimating spreadsheet is attached at Appendix 5.

A plan showing the existing sewer infrastructure and the proposed sewer infrastructure options is attached as **Appendix 4**.

3.1 Design Sewerage Loading

Design flows for development have been estimated using values provided by GSC to determine theoretical loadings in equivalent tenements (ET). An ET is the theoretical sewage flow from an average residential lot.

The criteria used to determine theoretical sewer design flows are summarised

below:

Sewer loadings for the proposed industrial subdivision have been determined based on 6ET/Ha and are detailed in **Table 2** below.

- ☐ Average Dry Weather Flow (ADWF) = 0.0111/s per ET
- ☐ Peak Dry Weather Flow (PDWF) = ADWF x 'r'
- ☐ Storm Allowance = 0.058 l/s per ET (for gravity systems)
- □ Peak Wet Weather Flow (PWWF) = PDWF + SA

Note: 'r' factor is from an empirical relationship based on ET.

Table 2 Overall Sewer Loadings

Stage	Yield	ADWF	r	PDW F	SA	PWWF
	(ET)	(L/s)		(L/s)	(L/s)	(L/s)
1	108	1.18	3.21	3.78	6.26	10.04
2	186	2.05	2.94	6.02	10.79	16.81
Total	294	3.23	2.74	8.86	17.05	25.91



4.0 Conclusion

Investigations indicate that there are existing GSC water and sewer systems in the area that can be extended to service the proposed industrial subdivision.

The existing water systems can be extended in a manner to facilitate the future subdivision of the area.

Modelling indicates that water pressures in the area will achieve GSC requirements.


It is noted that it is proposed to construct a water treatment facility within the proposed subdivision and water pressures would be able to be adjusted from this facility.

A sewer network to service the proposed subdivision connecting to existing infrastructure is required to be constructed.

It is noted that existing infrastructure downstream of the proposed sewer connection point has not been analysed and the adequacy of the system will need to be checked during the detail design phase of the project.




Appendix I Subdivision Site Plan





Appendix 2 Water Infrastructure





Appendix 3 Water Modelling Outputs



Average Day Flows

Network Table - Nodes at 3:00 Hrs

	Elevation	Base Dema	Demand	Head	Pressure
Node ID	m	LPS	LPS	m	m
Resvr 1	312	#N/A	-1.88	312	0
Junc 2	289.5	0	0	311.99	22.49
Junc 3	288.7	0.82	0.61	311.98	23.28
Junc 6	288	0	0	311.99	23.99
Junc 4	286.2	0.84	0.63	311.98	25.78
Junc 7	286	0	0	311.99	25.99
Junc 5	285.7	0.84	0.63	311.98	26.28

Network Table - Nodes at 13:30 Hrs

	Elevation	Base Dema	Demand	Head	Pressure
Node ID	m	LPS	LPS	m	m
Resvr 1	312	#N/A	-5.67	312	0
Junc 2	289.5	0	0	311.96	22.46
Junc 3	288.7	1.453	1.89	311.87	23.17
Junc 6	288	0	0	311.94	23.94
Junc 4	286.2	1.453	1.89	311.85	25.65
Junc 7	286	0	0	311.94	25.94
Junc 5	285.7	1.453	1.89	311.85	26.15


Fire Flows @ Node 3

Network Table - Nodes at 13:30 Hrs

	Elevation	Base Dema	Demand	Head	Pressure
Node ID	m	LPS	LPS	m	m
Resvr 1	312	#N/A	-11.77	312	0
Junc 2	289.5	0	0	311.83	22.33
Junc 3	288.7	6.15	8	311.41	22.71
Junc 6	288	0	0	311.79	23.79
Junc 4	286.2	1.453	1.89	311.44	25.24
Junc 7	286	0	0	311.79	25.79
Junc 5	285.7	1.453	1.89	311.52	25.82



Appendix 4 Sewer Infrastructure





Appendix 5 Estimating Spreadsheets

PRELIMINARY ESTIMATING FORM SEWER PUMPING STATIONS

PROJECT DESCRIPTION:

em No.	Item Description	Qty	Unit	D (A) (
1			Oilit	Rate \$/unit	Amount \$
	Preliminary Items				·
	(a)Site Establishment and Disestablishment (Refer Table 8)	Item	Lump Sum		15000
	(b)Preparation and implementation of the Construction EMP, undertake environmental induction of all employees and proposed subcontractors. (Refer Table 7)	Item	Lump Sum		3000
	(c)Preparation and implementation of the Safety Management Plan. (Refer Table 7)	Item	Lump Sum		5000
	(d)Preparation and implementation of the Traffic Control Plan. (Refer Table 7)	Item	Lump Sum		NA
2	Civil Works - Sewage Pump Station (1.5m dia to 8m dia.) (Table 1) Clear, excavate and backfill in OTR conditions and construct pipework and pump station wet well (depth measured from top roof to top floor slab) complete with aluminium hatch covers, screens and ancillary metal work and fittings. Supply and place concrete formwork, steel reinforcement, concrete for pump station, roof slab, and concrete	Item	Lump Sum		258000
3	thrust blocks. Pumps for Sewage Pumping Stations - Supply and install pumps	пеш	Lump Sum		25650
3	and associated fittings, connection to pipework, testing and commissioning. (Refer Table 2)	Item	Lump Sum		20000
4	Electrical Switchboards for Sewage Pumping stations - Supply, fabrication and complete installation of electrical switchboard kiosk for sewage pump stations including connection to pumps, supply and install up to 25m of consumer mains from point of attachment(Refer Table 2)	Item	Lump Sum		60300
5	Telemetry for Sewage Pump Stations - Supply and install separate cabinet and controls in switchboard at pump station and connect, test and commission to enable control of the pump station operation as part of the HWC telemetry network. (Refer Table 2)	Item	Lump Sum		28400
6	Restoration of Surfaces (refer Table 3):				NA
7	Area Allowances - Extra over Item 2 for Sewage pump station area classification (Refer Table 4):	Item	Lump Sum		NA
8	Terrain Allowances - Extra over Item 2 for sewer pump station area classification. (Refer Table 5):	Item	Lump Sum		NA
9	Extra over Item 2 for Excavation below design depth including disposal of excavated material in the relevant area classification (Refer Table 6):		m3		NA
10	Extra over Item 2 for Excavation in rock (Refer Table 6)		m3		NA
11	Extra over Item 2 for Cut and fill earthworks including compaction (Refer Table 6):		m3		NA
12	Extra over Item 2 for Supply & place ballast (Refer Table 6)		tonne		NA
13	Extra over Item 2 for Importing and placement of select fill including compaction (Refer Table 6):		m3		NA
14	Supply all material and labour to undertake the access road(min 4m wide) and hardstand (Refer table 6):				
	(a) Prepare subgrade	40	m2	4.2	168
	(b) Supply, place and compact 150mm thick basecourse	40	m2	31	1240
	(e) Supply, place and compact two coat bitumen seal	40	m2	19	760
15	Dewatering for the following: (Table 6):				NA
16	Supply all plant, material and labour to undertake the following Piling works (Refer table 6):				NA
17	Supply al plant, material and labour to undertake the following Retaining Wall works (Refer table 6):				NA

19	Supply and Install valve pit concrete formwork, steel reinforced	Itom	Lump Sum	7280		
20	Supply and Install additional pipe Items outside station(Refer Table 6)	Item Item	Lump Sum	7260 NA		
21	Supply and install additional pipe items outside station(Refer Table 6) Supply and install additional pipework items inside station (Refer table	пеш	Lump Sum	NA NA		
22	Supply and install Type 2 or 4 flow refief structures in accordance with	Item	Lump Sum	NA NA		
22	Drgs SCp-502 and SCP-505 (Refer Table 6)	ILEIII	Lunip Sum	INA		
23	Supply and install emergency storage structures (Refer Table 6)		L/m	NA		
24	Supply and install fan forced ventilation (Refer Table 7)	Item	Lump Sum	NA		
25	Supply and install Soil Bed Filter (Refer Table 7)	Item	Lump Sum	NA		
26	Supply and install Odour Control - Iron Salts Dosing (Refer Table 7)	Item	Lump Sum	NA		
27	Supply all power to the site(point of attachment) by Energy Aust (Refer Table 7)	Item	Lump Sum	NA		
28	Pre commissioning and commissioning (Refer Table 7)	Item	Lump Sum	8000		
29	Work as Executed Drawings (Refer Table 7)	Item	Lump Sum	6000		
30	Preparation and submission of Operation and Maintenance Manuals (Refer Table 7)	Item	Lump Sum	4000		
31	Land Matters (Refer Table 12)	Item	Lump Sum	NA		
A.	TOTAL ESTIMATED CONTRACT AWARD SUM			422798		
В.	PRE-CONSTRUCTION COST (Table 10) Design Project management of Design Sub Total(B1) Pre-Construction Contingency (30% of B1)			50735.76 6088.2912 56824.0512 17047.21536		
	TOTAL PRE-CONSTRUCTION COST (B)			\$73,871.27		
C.	C. CONSTRUCTION COST Total Estimated Contract Award Sum (A) Construction Management (Table 11) Sub Total (C1)					
	Construction contingency (Table 12) (30% of C1)			139523.34		
	TOTAL CONSTRUCTION COST (C)			\$604,601.14		
	TOTAL PRELIMINARY PROJECT ESTIMATE (B+C)			\$678,472.41		

\$680,000.00

SEWER GRAVITY & RISING MAINS – PRELIMINARY

PROJECT DESCRIPTION: 361 Oxley Highway, Gilgandra

Detailed Estimate

				Detailed Estimate		
Item No.	Item Description	Qty	Unit	Rate \$/unit	Amount \$	
1	Site Establishment (Refer Table 9)	Item	Lump Sum		15,000	
2	Site Disestablishment (Refer Table 9)	Item	Lump Sum		15,000	
3	Preparation and implementation of the Construction EMP, undertake environmental induction of all employees and proposed sub-	Item	Lump Sum			
4	contractors. OHS&R Management				3000	
4.1	Preparation and implementation of the Safety Management Plan.	Item	Lump Sum		5000	
4.2	Extra over item 4.1 above for preparation and implementation of the	Item	Lump Sum		3000	
	Traffic Control Plan.		'			
5	Construction of Sewer Gravity Mains (Refer Table 1) Field Investigation and verification of depth and location of services					
	along pipeline route including liaison with relevant authorities and				3000	
5.1	arranging relocation and adjustment where required	Item	Lump Sum			
5.2	Supply all pipe materials including detector tape, pipe protection wrapping, rubber rings and lubricant for following pipe sizes (Refer Table 1):					
	PVC Sewer Gravity Main Class SN8:					
	a) Nominal DN 100 mm		m		0	
	b) Nominal DN 150 mm	958	m	11	10538	
	c) Nominal DN 225 mm					
	e) Nominal DN 300 mm		m		0	
	f) Nominal DN 375 mm		m		0	
	Flowtite GRP Sewer Gravity mains					
	g) Nominal DN 450 mm	201	m	320	64320	
	h) Nominal DN 525 mm		m		0	
	i) Nominal DN 600 mm		m		0	
	j) Nominal DN 675 mm		m		0	
	k) Nominal DN 750 mm		m		0	
	RC Sewer Gravity Mains					
	I) Nominal DN 900 mm		m		0	
	m) Nominal DN 1050 mm		m		0	
	n) Nominal DN 1200 mm		m		0	
5.3	Supply all pipe fittings including gaskets and ss bolts (Refer table 1):	Item	Lump Sum		NA	
5.4	Clear, excavate and backfill in OTR conditions at nominal depth up to 1.5m depth to invert for sewer gravity pipelines with pipe support Type 1 or 3 & Drawing SCP-200, trench support and disposal of excess excavated material including environmental erosion and sediment control. Includes lay, bed, compact, joint and test. Includes initial cleanup of disturbed areas of disturbed areas. Supply of materials, including construction of bulkheads and trenchstops for following pipe sizes:					
	PVC Sewer Gravity Main Class SN8:					
	a) Nominal DN 100 mm	050	m	75	0	
	b) Nominal DN 150 mm	958	m	75	71850	
	c) Nominal DN 225 mm		m		0	
	e) Nominal DN 300 mm		m		0	
	f) Nominal DN 375 mm Sewer Gravity mains		m		0	
	•	201		120	27939	
	g) Nominal DN 450 mm h) Nominal DN 525 mm	201	m	139	2/939	
	i) Nominal DN 600 mm		m m		0	
	j) Nominal DN 675 mm		m		0	
	k) Nominal DN 750 mm		m		0	
	RC Sewer Gravity Mains				<u> </u>	
	I) Nominal DN 900 mm				0	
	m) Nominal DN 1050 mm		1		0	
	n) Nominal DN 1200 mm		1		0	
5.5	Extra over Item 5.3 for clearing of heavily tree covered areas including				NA	
5.6	disposal of trees and rubbish from site Extra over Item 5.3 for constructing pipelines under high voltage		m2		NA NA	
	powerlines for the following pipe sizes:]	

Ī	PVC Sewer Gravity Main Class SN8:		Ī	Ī	1
	a) Nominal DN 100 mm		m		0
-	b) Nominal DN 150 mm		m		0
	c) Nominal DN 225 mm		m		0
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	Sewer Gravity mains				
	g) Nominal DN 450 mm		m		0
	h) Nominal DN 525 mm		m		0
	i) Nominal DN 600 mm		m		0
	j) Nominal DN 675 mm		m		0
	k) Nominal DN 750 mm		m		0
	RC Sewer Gravity Mains				
	I) Nominal DN 900 mm		m		0
	m) Nominal DN 1050 mm		m		0
-	n) Nominal DN 1200 mm		m		0
5.7	Extra over Item 5.3 for constructing pipelines in close proximity to existing underground power, gas and telecommunications/optic fibre cables for the following pipe sizes: PVC Sewer Gravity Main Class SN8:				NA
	a) Nominal DN 100 mm		m		0
—	b) Nominal DN 150 mm		m		0
——	c) Nominal DN 225 mm		m		0
——	e) Nominal DN 300 mm		m		0
—	f) Nominal DN 375 mm		m		0
——	Sewer Gravity mains				
-	g) Nominal DN 450 mm		m		0
	h) Nominal DN 525 mm		m		0
	i) Nominal DN 600 mm		m		0
	j) Nominal DN 675 mm		m		0
	k) Nominal DN 750 mm		m		0
	RC Sewer Gravity Mains				
	I) Nominal DN 900 mm				
-	m) Nominal DN 1050 mm				
	n) Nominal DN 1200 mm				
5.8	Extra over rate to Item 5.3 for Terrain allowance (Refer Table 6) for			ì	NA
	the following pipe sizes:				
-	(a) Nominal DN 100		m		0
	(b) Nominal DN 150		m		0
	(c) Nominal DN 225		m		0
	(d) Nominal DN 300		m		0
	(e) Nominal DN 375 (f) Nominal DN 450		m		-
			m		0
	(g) Nominal DN 525 (h) Nominal DN 600		m		0
	,		m		
	(i) Nominal DN 675 (j) Nominal DN 750		m m		0
	(j) Nominal DN 750 (k) Nominal DN 900		m m		0
	(I) Nominal DN 1050		m m		0
	(m) Nominal DN 1200		m		0
5.9	Extra over rate to Item 5.3 for additional excavation at depths to invert greater than 1.5m for the following pipe sizes for relevant area classification and and range of depth (Refer Table 2):				Ü
	(a) Nominal DN 150 - >(1.5-3.00)	480	m	28	13440
	(b) Nominal DN 150 - >(3.5-4.0)	278	m	68	18904
	(c) Nominal DN 225		m		0
			m	I	0
	(d) Nominal DN 300				_
	(e) Nominal DN 375		m		0
	(e) Nominal DN 375 (f) Nominal DN 450	201	m m	127	25527
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525	201	m m m	127	25527 0
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525 (h) Nominal DN 600	201	m m m	127	25527 0 0
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525 (h) Nominal DN 600 (i) Nominal DN 675	201	m m m m	127	25527 0 0 0
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525 (h) Nominal DN 600 (i) Nominal DN 675 (j) Nominal DN 750	201	m m m m	127	25527 0 0 0 0
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525 (h) Nominal DN 600 (i) Nominal DN 675 (j) Nominal DN 750 (k) Nominal DN 900	201	m m m m m	127	25527 0 0 0 0 0
	(e) Nominal DN 375 (f) Nominal DN 450 (g) Nominal DN 525 (h) Nominal DN 600 (i) Nominal DN 675 (j) Nominal DN 750	201	m m m m	127	25527 0 0 0 0

5.1	Restoration of Surfaces (refer Table 5):		NA .
	(a) Concrete kerb & gutter	m2	0
	(b) Concrete driveway	m2	0
	(c) Exposed aggregate & stamped driveway	m2	0
	(d) Concrete footpath	m2	0
	(e) Bitumen footpath	m2	0
	(f) Gravel pavement	m2	0
	(g) Standard bitumen pavement	m2	0
	(h) High-class bitumen pavement	m2	0
	(i) Pavers	m2	0
	(j) Turf	m2	0
	(k) Grass seeding	m2	0
5.11	Excavate, backfill, supply and install access chambers including base, chamber, cover & surround and access ladder for the following nominal diameter access chambers:		NA
	(a) Nominal DN 1000	each	0
	(b) Nominal DN 1500	each	0
	(c) Nominal DN 1800	each	0
5.12	Supply and install geotextile for the following pipe diameters:		NA
	(a) Nominal DN 100	m	0
	(b) Nominal DN 150	m	0
	(c) Nominal DN 200	m	0
	(d) Nominal DN 225	m	0
	(e) Nominal DN 300	m	0
	(f) Nominal DN 375	m	0
	(g) Nominal DN 450	m	0
	(h) Nominal DN 525	m	0
	(i) Nominal DN 600	m	0
	(j) Nominal DN 675	m	0
	(k) Nominal DN 750	m	0
	(I) Nominal DN 900	m	0
	(m) Nominal DN 1050	m	0
	(n) Nominal DN 1200	m	0
	(o) Nominal DN 1350	m	0
5.13	Extra over item 5.3 for Excavation in rock and disposal of excess excavated material(Refer Table 7)	m3	NA
5.14	Extra over rate to Item 5.3 for Additional compaction (Refer Table 7)	m3	NA
5.15	Extra over rate to Item 5.3 for Excavate below specified design depth where directed including disposal of excess excavated material(Refer Table 7)	m3	NA
5.16	Extra over Item 5.3 to Supply & place & compact sand (Refer Table 7)	m3	NA
5.17	Extra over Item 5.3 for supply, place and compact stabilised sand cement (14:1) backfill		NA
5.18	Extra over rate to Item 5.3 for Supply & place ballast including disposal of excess excavated material (Refer Table 7)	m3	NA
5.19	Extra over Item 5.3 for Supply, place and compact aggregate (Refer Table 7)	m3	NA
5.2	Dewatering of trench including establishment & disestablishment (Table 7)	m	NA
5.21	Acid sulphate and Contaminated soil (Table 7)		
	(a)Testing, Handling and treatment of acid sulphate soils	m3	NA
	(b) Initial testing for acid sulphate soils and prepare and submit report	each test	NA
	(c) Disposal off site of contaminated soil	m3	NA
5.22	Road crossing (refer Table 7)		
	(a) Thrust bore/directional drilling	m	NA
	(b) Road pavement backfill, compaction and surface restoration	m	NA
5.23	Extra over iten 5.21 for thrust boring/directional drifting under existing rail line (refer table 7, note 7)	m	NA
5.24	Supply and installation of pipe river crossing including supply of MSCL pipe, internal and external welding, testing of welds and 150 thick concrete encasement. Also includes mobilisation and demobilisation of dredge(if required) excavation & disposal of excavated material, backfilling, lay, bed and test for the following MSCL pipe sizes: (Refer Table 7)		NA
	(a) Nominal DN 300 MSCL	m	0
	(b) Nominal DN 375 MSCL	m	0

	(c) Nominal DN 450 MSCL		m		0
	(d) Nominal DN 500 MSCL		m		0
	(e) Nominal DN 600 MSCL		m		0
5.25	Supply and installation of pipe aerial creek crossing including supply of				NA
	MSCL pipe with protection coating, internal and external welding, testing of welds for the following MSCL pipe sizes: (Refer Table 7)				
	(a) Nominal DN 300 MSCL		m		0
	(b) Nominal DN 375 MSCL		m		0
	(c) Nominal DN 450 MSCL		m		0
	(d) Nominal DN 500 MSCL		m		0
	(e) Nominal DN 600 MSCL		m		0
5.26	Preparation of line sheets (Refer Table 8)	16	each	92	1472
5.27	Acceptance testing - gravity main (Refer Table 8)	1158	m	1.3	1505.4
5.28	Land Matters (Refer Table 13)	Item	Lump Sum	1.0	NA
0.20	Sub Total Sewer Gravity Mains	nom	Eurip Guin		279495.4
	ous rotal ocacl cravity mains				270400.4
6	Construction of Sewer Rising Mains (Table 1)				
6.1	Field Investigation and verification of depth and location of services along pipeline route including liaison with relevany authorities and arranging relocation and adjustment where required	Item	Lump Sum		3000
6.2	Supply all pipes materials, including detector tape, pipe protection wrapping, rubber rings and lubricant for following pipe sizes (Refer Table 1):				3000
	PVC Sewer Rising Main Class 12:				
	a) Nominal DN 100 mm		m		0
	b) Nominal DN 150 mm	730	m	26	18980
	c) Nominal DN 200 mm		m		0
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	DICL Sewer Rising mains Class 9				
	g) Nominal DN 100 mm		m		0
	h) Nominal DN 150 mm		m		0
	i) Nominal DN 200 mm		m		0
	j) Nominal DN 250 mm		m		0
	k) Nominal DN 300 mm		m		0
	I) Nominal DN 375 mm		m		0
	m) Nominal DN 450 mm		m		0
	n) Nominal DN 500 mm		m		0
	o) Nominal DN 600 mm		m		0
	p) Nominal DN 750 mm		m		0
	MSCL Sewer Rising Mains				
	q) Nominal DN 900 mm		m		0
6.3	Supply all pipe fittings including gaskets and ss bolts (Refer table 1):	Item	Lump Sum		
6.4	Clear, excavate and backfill in OTR conditions at nominal depth up to 1.5m depth to invert for sewer rising mains with pipe support Type 1 or 3 & Drawing SCP-200, trench support and disposal of excess excavated material including environmental erosion and sediment control. For steel pipes internal and external welding and testing of welds. Includes lay, bed, compact, joint and test. Includes initial cleanup of disturbed areas of disturbed areas. Supply of materials, including construction of bulkheads and trenchstops for following pipe sizes:		m		NA
	PVC Sewer Rising Main Class 12:				
	a) Nominal DN 100 mm		m		0
	b) Nominal DN 150 mm	730	m	68	49640
	c) Nominal DN 200 mm		m		0
	d) Nominal DN 250 mm		m		0
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	DICL Sewer Rising Mains Class K9				NA
	g) Nominal DN 100 mm		m		0
	h) Nominal DN 150 mm		m		0
_	i) Nominal DN 200 mm		m		0
	j) Nominal DN 250 mm		m		0
	k) Nominal DN 300 mm		m		0
	I) Nominal DN 375 mm		m		0

	m) Nominal DN 450 mm	Ī	m		0
	n) Nominal DN 500 mm		m		0
	o) Nominal DN 600 mm		m		0
	p) Nominal DN 750 mm		m		
	MSCL Sewer Rising Mains				
	g) Nominal DN 900 mm		m		0
6.5	Extra over Item 6.5 for clearing of heavily tree covered areas including				NA
0.0	disposal of trees and rubbish from site		m2		
6.6	Extra over Item 6.5 for constructing pipelines under high voltage				
	powerlines for the following pipe sizes:				NA
	PVC Sewer Rising Main Class 12:				
	a) Nominal DN 100 mm		m		0
	b) Nominal DN 150 mm		m		0
	c) Nominal DN 200 mm		m		0
	d) Nominal DN 250 mm		m		0
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	DICL Sewer Rising Mains Class K9				NA
	g) Nominal DN 100 mm		m		0
	h) Nominal DN 150 mm		m		0
	i) Nominal DN 200 mm		m		0
	j) Nominal DN 250 mm	 	m		0
	k) Nominal DN 300 mm	 	m		0
	I) Nominal DN 375 mm	 	m		0
	m) Nominal DN 450 mm				0
	n) Nominal DN 450 mm	 	m m		0
	*		m		0
	o) Nominal DN 600 mm		m		-
	p) Nominal DN 750 mm		m		0
	MSCL Sewer Rising Mains				NA
	q) Nominal DN 900 mm		m		0
6.7	Extra over Item 6.5 for constructing pipelines in close proximity to				
	existing underground power, gas and telecommunications/optic fibre cables for the following pipe sizes:				NA
	PVC Sewer Rising Main Class 12:				
	a) Nominal DN 100 mm		m		0
	b) Nominal DN 150 mm		m		0
	c) Nominal DN 200 mm				0
	d) Nominal DN 250 mm		m		0
	*		m		
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	DICL Sewer Rising Mains Class K9				NA
	g) Nominal DN 100 mm		m		0
	h) Nominal DN 150 mm		m		0
	i) Nominal DN 200 mm		m		0
	j) Nominal DN 250 mm		m		0
	k) Nominal DN 300 mm		m		0
	I) Nominal DN 375 mm		m		0
	m) Nominal DN 450 mm		m		0
	n) Nominal DN 500 mm		m		0
	o) Nominal DN 600 mm	Ì	m		0
	p) Nominal DN 750 mm		m		0
	MSCL Sewer Rising Mains	 			NA
	g) Nominal DN 900 mm	 	m		0
6.8	Extra over rate to Item 6.5 for Terrain allowance (Refer Table 6) for				
5.5	the following pipe sizes:				NA
	a) Nominal DN 100 mm		m		0
	b) Nominal DN 150 mm	350	m	90	31500
	c) Nominal DN 200 mm		m		0
	d) Nominal DN 250 mm		m		0
	e) Nominal DN 300 mm		m		0
	f) Nominal DN 375 mm		m		0
	g) Nominal DN 450 mm	-	m		0
	h) Nominal DN 500 mm	<u> </u>			0
	*		m		
	i) Nominal DN 600 mm	<u> </u>	m		0
	j) Nominal DN 750 mm		m		0
	k) Nominal DN 900 mm		m		0

6.9	Extra over rate to Item 6.5 for additional excavation at depths to invert			
	greater than 1.5m for the following pipe sizes in the relevant area			
	classification (Refer Table 2):			
	a) Nominal DN 100 mm		m	0
	a) Nominal DN 150 mm		m	0
	a) Nominal DN 200 mm		m	0
	b) Nominal DN 250 mm		m	0
	c) Nominal DN 300 mm		m	0
	d) Nominal DN 375 mm		m	0
	e) Nominal DN 450 mm		m	0
	f) Nominal DN 500 mm		m	0
	g) Nominal DN 600 mm		m	0
	h) Nominal DN 750 mm		m	0
	i) Nominal DN 900 mm		m	
6.1	Restoration of Surfaces (refer Table 5):			
	(
	(a) Concrete kerb & gutter		m2	0
	(b) Concrete driveway		m2	0
	(c) Exposed aggregate & stamped driveway		m2	0
	(d) Concrete footpath		m2	0
	(e) Bitumen footpath		m2	0
	(f) Gravel pavement		m2	0
	(g) Standard bitumen pavement		m2	0
				_
	(h) High-class bitumen pavement		m2	0
	(i) Pavers		m2	0
	(j) Turf		m2	0
	(k) Grass seeding		m2	0
6.11	Supply and install geotextile for the following pipe diameters:			
				NA
	(a) Nominal DN 100		m	0
	(b) Nominal DN 150		m	0
	(c) Nominal DN 200		m	0
	(d) Nominal DN 225		m	0
	(e) Nominal DN 300		m	0
	(f) Nominal DN 375			0
	· /		m	
	(g) Nominal DN 450		m	0
	(h) Nominal DN 525		m	0
	(i) Nominal DN 600		m	0
	(j) Nominal DN 675		m	0
	(k) Nominal DN 750		m	0
	(I) Nominal DN 900		m	0
	(m) Nominal DN 1050		m	0
	(n) Nominal DN 1200		m	0
	(o) Nominal DN 1350		m	0
6.12	Extra over item 6.5 for Excavation in rock and disposal of excess		m3	NA
	excavated material(Refer Table 7)			
6.13	Extra over rate to Item 6.5 for Additional compaction (Refer Table 7)		m3	NA
6.14	Extra over rate to Item 6.5 for Excavate below specified design depth		m ²	NA
U. 14	where directed including disposal of excess excavated material(Refer		m3	INA
	Table 7)		<u> </u>	
6.15	Extra over Item 6.5 to Supply & place & compact sand (Refer Table		m3	NA
	7)			
6.16	Extra over Item 6.5 for supply, place and compact stabilised sand		m3	 NA
6.17	cement (14:1) backfill Extra over Item 6.5 for Supply, place and compact aggregate (Refer		mo	NA
0.17	Table 7)		m3	INA
6.18	Extra over rate to Item 6.5 for Supply & place ballast including		m3	NA
-	disposal of excess excavated material (Refer Table 7)			
	, , ,			
6.19	Dewatering of trench including establishment & disestablishment		m	 NA
6.2	(Table 7)		 	NA
U.Z	Acid sulphate and Contaminated soil			
	(a)Testing, Handling and treatment of acid sulphate soils		m3	NA
	(b) Initial testing for acid sulphate soils and prepare and submit report		each test	NA
			_	NA
	(c) Disposal off site of contaminated soil		m:x	
6.21	(c) Disposal off site of contaminated soil Supply and place treated timber piling for pipe support	Item	m3 Lump Sum	NA

	(a) Trust bore/directional drilling		m		0
	(b) Road pavement backfill, compaction and surface restoration		m		0
6.23	Extra over item 6.23 for thrust boring/directional drilling under existing rail line (refer table 7, note 7)		m		0
6.24	Supply and installation of pipe river crossing including supply of MSCL pipe, internal and external welding, testing of welds and 150 thick concrete encasement. Also includes mobilisation and demobilisation of dredge(if required) excavation & disposal of excavated material, backfilling, lay, bed and test for the following MSCL pipe sizes: (Refer Table 7)				NA
	(a) Nominal DN 300 MSCL		m		0
	(b) Nominal DN 375 MSCL		m		0
	(c) Nominal DN 450 MSCL		m		0
	(d) Nominal DN 500 MSCL		m		0
	(e) Nominal DN 600 MSCL		m		0
6.25	Supply and installation of pipe aerial creek crossing including supply of MSCL pipe with protection coating, internal and external welding, testing of welds for the following MSCL pipe sizes: (Refer Table 7)				NA
	(a) Nominal DN 300 MSCL		m		0
	(b) Nominal DN 375 MSCL		m		0
	(c) Nominal DN 450 MSCL		m		0
	(d) Nominal DN 500 MSCL		m		0
	(e) Nominal DN 600 MSCL		m		0
6.26	Supply and Install additional pipe Items (Refer Table 8)	Item	Lump Sum		
6.27	Supply and install additional DICL fittings (Refer Table 8)	Item	Lump Sum		NA
6.28	Supply and Install valve pits (Refer table 8)	Item	Lump Sum		NA
6.29	Supply and construct vent stacks (Refer Table 8)	1	each	8500	8500
6.3	Preconstruction record (Refer Table 8)				
	(a) Photographic	730	m	0.6	438
	(b) Video		m		0
6.31	Work as Executed Drawings (Refer Table 8)	Item	Lump Sum		17200
6.32	Preparation of line sheets (Refer Table 8)		m		0
6.33	Acceptance testing - gravity main (Refer Table 8)		each		0
6.34	Land Matters (Refer Table 13)	Item	Lump Sum		NA
	Sub Total Sewer Rising Mains				132258
•	Sub Total Sewer Gravity Mains & Sewer Rising Mains		-		411753.4
	TOTAL ESTIMATED CONTRACT AWARD SUM				411753.4

B. PRE-CONSTRUCTION COST (Table 10)

 Design
 49410.408

 Project management of Design
 9882.0816

 Sub Total(B1)
 59292.4896

 Pre-Construction Contingency (20% of B1)
 11858.49792

TOTAL PRE-CONSTRUCTION COST (B) \$130,443.48

C. CONSTRUCTION COST

 Total Estimated Contract Award Sum (A)
 411753.4

 Construction Management (Table 11)
 41175.34

 Sub Total (C1)
 452928.74

 Construction contingency (Table 12) (20% of C1)
 90585.748

Construction contingency (Table 12) (20% of C1) 90585.748

TOTAL CONSTRUCTION COST (C) \$543,514.49

TOTAL PRELIMINARY PROJECT ESTIMATE (B+C)	\$673,957.97
--	--------------

WATER RETICULATION & TRUNK MAINS – PRELIMINARY PROJECT DESCRIPTION:

361 Oxley Highway, Gilgandra

				Preliminary	
em No.	Item Description	Qty	Unit	Rate \$/unit	Amount \$
1	Site Establishment (Refer Table 9)	Item	Lump Sum		6000
2	Site Disestablishment (Refer Table 9)	Item	Lump Sum		6000
3	Preparation and implementation of the Construction EMP, undertake environmental induction of all employees and proposed subcontractors.	Item	Lump Sum		3000
4	OHS&R Management				
4.1	Preparation and implementation of the Safety Management Plan.	Item	Lump Sum		5000
4.2	Extra over item 4.1 above for preparation and implementation of the Traffic Control Plan.	Item	Lump Sum		3000
5	Construction of Reticulation watermains (Refer Table 1)				
5.1	Field Investigation and verification of depth and location of services along pipeline route including liaison with relevant authorities and arranging relocation and adjustment where required	Item	Lump Sum		2,500
5.2	Supply all pipes materials including detector tape, pipe protection wrapping, rubber rings and lubricant for following pipe sizes (Refer Table 1):				
	a) Nominal DN 150 mm PVC class 16 pipe.	928	m	26	24128
5.3	Supply all pipe fittings including gaskets and ss bolts (Refer Table 1):	Item	Lump		
5.4	Clear, excavate and backfill in OTR conditions at nominal depth up to 1.5m depth to invert for reticulation pipelines with pipe support Type B or D & Drawing WCP-202 and disposal of excess excavated material including environmental erosion and sediment control. Includes Lay, bed, joint and test. Includes initial cleanup of disturbed areas and consumer service connections. Supply of materials, including detector tape, pipe protection wrapping and construction of thrust restraints, bulkheads and trenchstops for following pipe sizes (Refer Table 1):				
	a) Nominal DN 150 mm PVC class 16 pipe.	928	m	59	54752
5.5	Extra over Item 5.5 for constructing pipelines under high voltage powerlines for the following pipe sizes:				na
5.6	Extra over Item 5.5 for constructing pipelines in close proximity to existing underground power, gas and telecommunications/optic fibre cables for the following pipe sizes:				na
5.7	Extra over Item 5.5 for clearing of heavily tree covered areas including disposal of trees and rubbish from site		m2		na
5.8	Supply additional service connection pipe and fittings and install (Refer Table 4)	Item	Lump Sum		na
5.9	Extra over rate to Item 5.5 for Terrain allowance (Refer Table 6) for the following pipe sizes:				na

	.		_		
5.10	Extra over rate to Item 5.5 for additional				na
	excavation at depths to invert greater than 1.5m including disposal of excess excavated material				
	for the following pipe sizes in the relevant area				
	classification (Refer Table 3):				
5.11	Restoration of Surfaces (refer Table 5):				na
5.12	Extra over item 5.5 for Excavation in rock and		m3		na
	disposal of excess excavated material(Refer				
	Table 7)				
5.13	Extra over rate to Item 5.5 for Additional		m3		na
5.14	compaction (Refer Table 7) Extra over rate to Item 5.5 for Excavate below		m2		
5.14	specified design depth where directed including		m3		na
	disposal of excess excavated material(Refer				
	Table 7)				
5.15	Extra over Item 5.5 to Supply & place & compact		m3		na
	sand (Refer Table 7)				
5.16	Extra over Item 5.5 for supply, place and compact		m3		na
5.17	stabilised sand cement (14:1) backfill		m2		no
J. 17	Extra over Item 5.5 for supply, place and compact aggregate (Refer Table 7)		m3		na
5.18	Extra over rate to Item 5.5 for Supply & place		m3		na
	ballast including disposal of excess excavated				
	material (Refer Table 7)				
5.19	Dewatering of trench including establishment and		m		na
	disestablishment (Table 7)				
5.2	Acid Sulphate Soil and Contamination (Refer				na
	Table 7)				
5.21	Supply and place treated timber piling for pipe	Item	Lump Sum	Ì	na
	support				
5.22	Road crossing (refer Table 7)				na
	Extra over item 5.23 (a) for thrust		m		na
5.23	boring/directional drilling under existing rail line				
	(Refer table 7, note 7) Supply and installation of pipe river crossing		1		na
	including supply of MSCL pipe, internal and				na
	external welding, testing of welds and 150 thick				
	concrete encasement. Also includes mobilisation				
	and demobilisation of dredge(if required)				
	excavation & disposal of excavated material,				
5.24	backfilling, lay, bed and test for the following MSCL pipe sizes: (Refer Table 7)				
5.25	Supply and installation of pipe aerial creek		1		na
0.20	crossing including supply of MSCL pipe with				
	protection coating, internal and external welding,				
	testing of welds. For the following MSCL pipe				
	sizes: (Refer Table 7)				
5.26	Supply and Install additional pipe Items (Refer	Item	Lump Sum		na
	Table 8) (Note: show all items for detailed estimate)				
5.27	Supply and install additional DICL fittings (Refer	Item	Lump Sum	1	na
J	Table 8) (Note: show all fittings for detailed	1.0/11	p Juiii		114
	estimate)				
5.28	Supply and Install valve pits (Refer table 8) (Note:	Item	Lump Sum	Ì	na
	show all pit sizes for detailed estimate)				
5.29	Supply and install a complete single flowmeter				na
	including in-ground concrete pit with aluminium covers and separate in-ground isolating stop				
	valves upstream of flowmeter with bypass. (Refer				
	Table 8)	Item	Lump Sum		
5.30	Preconstruction record (Refer Table 8)				
-	(a) Photographic	928	m	0.6	556.8
	(b) Video	020	m	0.0	0
E 24	. ,	000		0	
5.31	Work as Executed Drawings (Refer Table 8)	928	m	8	7424
5.32	Preparation of line sheets (Refer Table 8)	10	m	92	920
5.33	Land Matters (Refer Table 13)	Item	Lump Sum		na

5.34 Sub Total Reticulation Mains	113280.8
TOTAL ESTIMATED CONTRACT AWARD SUM (PRELIMINARY OR DETAILED)	113280.8
PRE-CONSTRUCTION COST (Table 10)	
Design	16992.12
Project management of Design	2039.0544
Sub Total(B1)	19031.1744
Pre-Construction Contingency (30% of B1)	5709.35232
TOTAL PRE-CONSTRUCTION COST (B)	\$24,740.53
CONSTRUCTION COST	
Total Estimated Contract Award Sum (A)	113280.8
Construction Management (Table 11)	20000
Sub Total (C1) Construction contingency (Table 12)	133280.8
(30% of C1)	39984.24
TOTAL CONSTRUCTION COST (C)	\$173,265.04
TOTAL PRELIMINARY PROJECT ESTIMATE	
(B+C) (PRELIMINARY OR DETAILED)	\$198,005.57

say \$200,000.00